401

KADUR DIVISION.

ADVERTISEMENT.

The 20th September 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 18th October 1887, for constructing houses for the officials of the Mudgere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement either in the form given below, showing the rates at which the different items specified will be executed or at——per cent less than the sanctioned estimate amount.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing houses for the officials of the Mudgere Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

FORM.

Description of Work.	Unit of Work.	Quantity.	Rate per Unit.
Earthwork (excavation)	C. Yd.	150	
Burnt stone in mud (foundation and basement) ..	C. Ft.	6,936	
Burnt brick in mud (superstructure exterior walls) ..	C. Ft.	4,770	
Raw brick in mud (do interior walls) ..	C. Ft.	6,326	
Burnt stone slabs, 3″ to 4″ thick (steps and lintels over doors and windows)	Sq. Ft.	549	
Junglewood work (reserved)	C. Ft.	384	
Roofing with junglewood reepers and Mangalore tiles..	Sq.	61·36	
Ridging with Mangalore tiles	R. Ft.	374	
Flooring with earth and gravel	Sq.	27·74	
Plastering with chunam (exterior walls).. ..	do	37·02	
Do with mud (interior walls) ..	do	132·27	
Whitewashing 2 coats interior walls ..	do	132·27	
Color washing 2 coats exterior walls	do	37·02	
Pointing in chunam (basement)	do	10·46	
Junglewood doors battened $3\frac{1}{2}' \times 6\frac{1}{2}'$ with frames, &c., complete	No.	36	
Do windows $2\frac{1}{2}' \times 3\frac{1}{2}'$ and wooden bars ..	No.	28	
Tarring junglewood resting on walls & ends of rafters ..	L. S.	..	
Clearing and levelling sites and making approach roads	..	..	

D. SITARAM RAO,
Offg. Executive Engineer.